Faculty of Engineering
Dept. of Architecture

Building Management systems as an Approach for Energy Conservation

With special reference to Buildings in Cairo

By

Arch. Fatma Ahmed Ahmed Elbony

As partial fulfillment of the requirements For PhD In Architecture

Under Supervision of

Prof. Dr. Morad Abd-Elkader
Professor of Architecture and Environmental Control
Faculty of Engineering – Ain Shams University

Prof. Dr. Maged Negm
Professor of Mechanical Engineering
Faculty of Engineering – Ain Shams University

Dr. Ahmed Atef
Assistant Professor of Architecture
Faculty of Engineering – Ain Shams University

2013

Index

List of Contents	i
List of Figures	vi
List of Tables	xx
Research Introduction and Summery	xxviii

Chapter 1	**Energy: Energy in Buildings**	
	Introduction	1
1-1	The Energy Situation in Egypt	1
	1-1-1 Energy Resources	1
	1-1-2 Energy Consumption	4
1-2	Energy Consumption in Buildings	8
	1-2-1 Energy Use in Buildings: Past, Present, and Future	8
	1-2-2 Industrial Revolution and Energy Use in Buildings	8
	1-2-3 Where does the Energy go?	10
1-3	Overall Energy Performance of a Building	13
1-4	Energy Conservation and Energy Efficiency	14
	1-4-1 Energy efficiency	14
	1-4-2 Energy conservation	15
	1-4-3 Current Situation of Energy Conservation	16
1-5	Demand for Energy Conservation in Buildings	17
	1-5-1 Energy Conservation and Climate Change	17
	1-5-2 Depletion of Energy Resources (Energy Crisis)	19
	Conclusion	20

Chapter 2	**Building Management System as an Active Approach for Energy Conservation**	
	Introduction	21
2	Literature review of Building Management System (BMS)	21
2-1	What is Modern Building Management System?	22
2-2	Designing building management systems	24
	2-2-1 Management Level	24
	2-2-2 Automation (Control) Level	24
	2-2-3 Field level	24
2-3	Function of modern BMS	25

2-4	BMS and Building Systems			26
2-5	Significance of Building management system in office buildings			28
2-6	Building Management system and Energy Conservation			29
2-7	Building Energy Management Systems			29
	2-7-1	Energy Management		30
	2-7-2	The Value of Energy Management		30
	2-7-3	Types of Building Energy Management Systems		30
	2-7-4	Components of Building Energy Management System		34
	2-7-5	Energy Savings Control strategies		36
	2-7-6	Operation of BEMS		40
	2-7-7	Maintenance of BEMS		41
	2-7-8	BENEFITS of BEMSs		42
	2-7-9	Advantages and Disadvantages of BEMS		43
	2-7-10	Building Energy Management System Costs		45
2-8	BEMS with Building Systems			46
	2-8-1	BEMS with Active Systems		46
	2-8-2	BEMS with Passive Systems		48
	Conclusion			49

Chapter 3	**Building Design Management as an Passive approach for Energy Conservation**			
	Introduction			50
3	Passive Approach for Energy Conservation in Buildings			50
3-1	Building Design process			51
	3-1-1	Design Process		52
	3-1-2	Definition of Design		52
3-2	Managing of Building Design			53
	3-2-1	Design Management Tasks		54
3-3	Building Design Approaches			56
	3-3-1	Conventional Building Design Approach		56
	3-3-2	Whole-Building Design Approach		59
3-4	Building Design and Energy Conservation			72
3-5	Passive Architecture			74
	3-5-1	Passive Design Strategies		75
		3-5-1-1	Passive Cooling	75
		3-5-1-2	Daylighting	80
	3-5-2	Passive Design Elements		82
		3-5-2-1	Building Orientation (Solar and Wind considerations)	82

		3-5-2-2	Space Planning	83
		3-5-2-3	Building form	83
	3-5-3	Building Envelope		84
		3-5-3-1	Opaque elements	85
		3-5-3-2	Non Opaque Building Envelope elements	86
		3-5-3-3	Fenestrations	88
		3-5-3-4	Shading Devices	89
	3-5-4	Building Materials		93
		3-5-4-1	Phases of Building Materials	93
		3-5-4-2	Building Materials and Energy Conservation	94
		3-5-4-3	Properties of Building Materials	95
		3-5-4-4	Smart Materials	100
		3-5-4-5	Environmental impacts of material use	101
	3-5-5	The Benefits of Passive Design		101
	3-5-6	Economic Feasibility of Passive Design		103
	Conclusion			105

Chapter 4	**Proposed an Integrated Methodology for Energy Management PIMEM in office buildings through both Design and Operation stage**		
	Introduction		106
4-1	Integration of Energy Management aspects in the design process		106
4-2	proposed an integrated Methodology for Energy Management		109
4-3	Objectives of the Proposed Methodology		110
4-4	The concept of the Proposed Methodology		110
4-5	Building Management System and Building Design Management		112
	4-5-1	Building Systems Design	112
	4-5-2	Architectural Design Management	113
4-6	plan of work for the proposed Methodology		113
	4-6-1	Preparation Stage (Pre Design Stage)	119
	4-6-2	Design Stage	122

Chapter 5	Examples and Case Study	
	Introduction	126
	Case Study 1: Stratus Computer	126
	Case Study 2: Bank of America Corporation (BAC), Banking center	129
	Case Study 3: Target's Greensborough store	132
	Case Study 5: Alaraby Bank	134
5-2	Field Study	134
5-3	Base Case	135
5-4	Data Gathering	135
	5-4-1 Weather data and Location	135
	5-4-2 Architectural Data	138
	5-4-3 Building operation Features	143
	Conclusion	164

Chapter 6	Implementing the Proposed Integrated Methodology PIMEM	
	Introduction	165
6	Simulation Process	166
6-1	Energy Simulation Software Selection	166
	6-1-1 Site data	167
	6-1-2 Weather Data	168
	6-1-3 Comfort Parameters	169
	6-1-4 Building Fabric	169
	6-1-5 Glass properties	170
	6-1-6 Mechanical system variables	170
6-2	Simulation Tool	171
6-3	Base Case Simulation	172
	6-3-1 Building Zoning	172
	6-3-2 Performance of the Building	176
	6-3-2-1 Actual Building Performance	176
	6-3-2-2 Simulated Building Performance	177
6-4	Improved Case	182
6-5	Outputs and representation forms	182
6-6	Specifying Independent Variables	183
6-7	Sensitivity to individual parameters	185
	6-7-1 Passive Design Strategies	185

		6-7-1-1	Passive Cooling	185
		6-7-1-2	Day Lighting	186
	6-7-2	Passive Cooling Techniques		188
		6-7-2-1	Building form	188
		6-7-2-2	Building orientation	188
		6-7-2-3	Building Envelope Parameters	232

Chapter 7	**Economic Feasibility of the Proposed Integrated Methodology PIMEM**	
	Introduction	316
7-1	Combined Parameters	316
7-2	Integrated Design Team	349
7-3	Economic Feasibility	350
	7-3-1 Initial Costs	350
	7-3-2 Annual running Costs	355
	Conclusion	359

Chapter 8	**Conclusions and Recommendations**	
	Conclusions	360
	Recommendations	367

List of Figures

Chapter 1	**Energy: Energy in Buildings**	
Figure 1-1	Oil production and consumption in Egypt 2008/2009	2
Figure 1-2	Natural Gas production and consumption in Egypt 2008/2009	3
Figure 1-3	Total Primary Energy productions (2007)	4
Figure 1-4	A map showing solar energy potential in Egypt	4
Figure 1-5	World Energy Consumption, history and projected	5
Figure 1-6	Energy Consumption by Source (2007)	6
Figure 1-7	Energy Intensity in MEDA-countries	7
Figure 1-8	Ancient models of primitive houses and shelters	8
Figure 1-9	Energy Consumption by sector 2005	9

Figure 1-10	Electrical Energy Consumption by sector in Cairo	10
Figure 1-11	Energy consumed in the life of a building, estimated at 60 years	10
Figure 1-12	Two charts showing the consumption of embodied energy for different building components, and typical energy consumption throughout the buildings life	11
Figure 1-13	Building operational costs lasts throughout its lifetime	12
Figure 1-14	How energy flows are linked in buildings	13
Figure 1-15	the factors upon which the energy performance depends Building, system and occupant factors affecting energy consumption in non-domestic buildings	13
Figure 1-16	Total Primary Energy production (2003-2004)	19
Figure 1-17	Total Primary Energy production (2007)	19

Chapter 2	**Building Management System as an Active Approach for Energy Conservation**	
Figure 2-1	Central Control Panels	21
Figure 2-2	A Typical Bas	23
Figure 2-3	Building automation, three-level	25
Figure 2- 4	Building Management System represents the brain for the building	26
Figure 2-5	Review of the building management system's functions at different levels	27
Figure 2-6	Occupant Sensor Control System	31
Figure 2-7	Programmable Electronic Thermostat	32
Figure 2-8	Photo Control	32
Figure 2-9	Components of a BEMS	35
Figure 2-10	Proportional reset schedule As the outside air temperature decrease, the chilled water temperature is reset to a higher	38
Figure 2-11	Direct load information reset In this reset schedule, the cooling load is based on the number of chilled water valves that are greater than 90 percent open	38
Figure 2-12	Buildings service systems that can be monitored, controlled and optimized by BEMS	39
Figure 2-13	Demand control system	39
Figure 2-14	Surveyed Prevalence and Usage Rates for Selected EMCS Functions	41
Figure 2-15	Commercial Buildings' Energy consumption Patterns in Egypt	47
Figure 2-16	Lighting control is based on illumination level and room presence (sensor C)	47
Figure 2-17	controlled window and lighting systems	48

Chapter 3	Building Design Management as an Passive approach for Energy Conservation	
Figure 3-1	The Markus/ Maver map of the design process	51
Figure 3-2	Vision statement	55
Figure 3-3	The Decision Pyramid. (Courtesy of Min Kantrowitz)	56
Figure 3- 4	The architectural facade recesses surrounding the south-facing windows that serves as window overhangs to shade the windows and minimize direct solar gains. Placing the windows at the top of these recesses further enhances the effectiveness of these overhangs.	56
Figure 3-5	Representation of the Integrated Design process	62
Figure 3-6	The phases of the Integrated Design	63
Figure 3-7	The integrated design starts much earlier in the project development process compared to conventional design, involving interaction with the owner to define issues and set goals prior to schematic design and continuing through construction and commissioning	64
Figure 3-8	Integrated Design Team	69
Figure 3-9	Implementation phase	72
Figure 3-10	Office buildings such as this, relying heavily on air-conditioning systems, often use 10 to 15 times more energy than the most energy efficient buildings	73
Figure 3-11	The original Low Energy Office at the BRE, built in 1983 and refurbished in 1991, now returns an energy cost of approximately £3.00 per annum, and daylight.	73
Figure 3-12	The relation between passive design strategies and passive design elements	76
Figure 3-13	Pressure effect from wind	77
Figure 3-14	Single sided ventilation	77
Figure 3-15	Cross ventilation effective for up to five times the ceiling height	77
Figure 3-16	cross ventilation ensure partitions are designed to minimize resistanc	77
Figure 3-17	Stack Ventilation	78
Figure 3-18	Cross section showing air flow of cross flow natural ventilation incorporating solar chimney	78
Figure 3-19	Solar Chimney	78
Figure 3-20	Plan of building Pedro de Valdivia. Santiago	79
Figure 3-21	Building Pedro de Valdivia. Santiago	79
Figure 3-22	Building Las Industries. Santiago	79
Figure 3-23	Cooling energy demand for building Pedro de Valdivia. Santiago	79
Figure 3-24	Cooling energy demand for building Las Industries. Santiago	79
Figure 3-25	Effective types of daylight apertures	80

Figure 3-26	A Well-daylight working environment not only saves energy but is also preferred by the occupants	81
Figure 3-27	Primary energy use for naturally ventilated and air-conditioned offices in the UK	81
Figure 3-28	Building Orientation and solar heat gain	82
Figure 3-29	Section of a building design case study for high-density commercial offices	83
Figure 3-30	The effect of envelope to volume ratio on energy efficiency	83
Figure 3-31	Monthly total electricity for electricity building with different Window to Wall Ratios at climatic condition of Cairo	88
Figure 3-32	glazing ratios (i.e. the percentage of glazing in a façade) has a significant impact on the energy use, as shown for a south-facing façade on an office building in the UK	89
Figure 3-33	a: External shading device b: Internal shading device	90
Figure 3-34	Three phases of the building material life cycle	94
Figure 3-35	Passive Architecture asserts Energy Conservation that reduces Operational Energy in building	102

Chapter 4	**Proposed an Integrated Methodology for Energy Management PIMEM in office buildings through both Design and Operation stage**	
Figure 4-1	Progress of building design showing stages at which thermal decisions are usually taken (Burberry 1983)	107
Figure 4-2	Key factors that influence energy Consumption	110
Figure 4-3	Building Energy equation	111
Figure 4- 4	The relation between Architectural Design Management and BMS	112

Chapter 5	**Examples and Case Study**	
Figure 5-1	Stratus Computer building	126
Figure 5-2	ENERGY USERS %	126
Figure 5-3	Energy Costs versus Production	127
Figure 5-4	Bank of America Corp (NYSE:BAC)	129
Figure 5-5	Bank of America Corp branch	130
Figure 5-6	Bank of America Corp branch	130

Figure 5-7	Target's Greensborough store	132
Figure 5-8	Target's Greensborough store	133
Figure 5-9	Alaraby Bank, perspective	134
Figure 5-10	Location of Alaraby Bank (Smart Village) Google Earth view with North Direction	135
Figure 5-11	Ground floor plan	138
Figure 5-12	First Floor Plan	139
Figure 5-13	Second Floor Plan	139
Figure 5-14	Alaraby Bank, Elevations	140
Figure 5-15	Types of glass that used for Alaraby bank fenestration	142
Figure 5-16	Types of lighting fixtures	143
Figure 5-17	Building Management System and HVAC system (AHU)	146
Figure 5-18	BMS Architecture	150
Figure 5-19	Air Handling Units	158
Figure 5-20	BMS Control Panels	158
Figure 5-21	Building Energy Meters	158
Figure 5-22	Print screen for BMS software	159

Chapter 6	**Implementing the Integrated Proposed Methodology IPMEM**	
Figure 6-1	Overview of EnergyPlus which explains the integration of EnergyPlus with other computer simulation software	167
Figure 6-2	Energy Plus elements	168
Figure 6-3	Building Geometry of the Energy plus Model	171
Figure 6- 4	Thermal Zones in the Basement floor	173
Figure 6-5	Thermal Zones in the Ground floor	173
Figure 6-6	Thermal Zones in the First Floor	174
Figure 6-7	Thermal Zones in the Second Floor	174
Figure 6-8	Actual Building Energy Consumption in 2011 as determined from meter readings	176
Figure 6-9	Annual heat gains and losses' sources in the actual case zones	178
Figure 6-10	Simulated Total Building Energy Consumption	179
Figure 6-11	Simulated Total Building Energy Consumption (a comparison Between Zones 1-2 &1-3, and zones 2-2 &2-3	180
Figure 6-12	Simulated Lights Electric Consumption	180
Figure 6-13	Architectural Design Parameters affecting Energy Consumption in	184

Figure 6-14	End-Use Energy Consumption through the Base Case	187
Figure 6-15	End-Use Energy Consumption through the building with Day lighting control	187
Figure 6-16	Cooling and lighting loads in the Existing building	187
Figure 6-17	Cooling and lighting loads in the Building with day lighting controls	187
Figure 6-18	Existing building orientation (35°) from North	189
Figure 6-19	Modified building orientation (20°) from North	189
Figure 6-20	Modified building orientation (10°) from North	189
Figure 6-21	Modified building orientation (0°) From North	189
Figure 6-22	Monthly cooling energy consumption through the four investigated orientations	191
Figure 6-23	Existing Building **(NW-SE- SW Zone** 0-2)	192
Figure 6-24	Reoriented Building 20° (**NW-SE- SW Zone** 0-2)	192
Figure 6-25	Reoriented Building 10 °(**NW-SE- SW Zone** 0-2)	192
Figure 6-26	Reoriented Building (**North-West- South Zone** 0-2)	192
Figure 6-27	Existing Building **(SW Zone** 0-3)	193
Figure 6-28	Reoriented Building 20° (**SW Zone** 0-3)	193
Figure 6-29	Reoriented Building 10 °(**SW Zone** 0-3)	193
Figure 6-30	Reoriented Building (**South Zone** 0-3)	193
Figure 6-31	Monthly cooling energy consumption For zone (0-2) in the four investigated orientations	196
Figure 6-32	A comparison between lighting loads for zone 02 through the base case without daylighting control and the other reoriented models with daylighting controls	197
Figure 6-33	A comparison between cooling loads for zone 0-2 through the base case without daylighting control, and the other reoriented models without daylighting control, and with daylighting control	197
Figure 6-34	Monthly cooling energy consumption For zone (0-3) in the four investigated orientations	199
Figure 6-35	A comparison between lighting loads for zone 0-3 through the base case without daylighting control and the other reoriented models with daylighting controls	200
Figure 6-36	A comparison between cooling loads for zone 0-3 through the base case without daylighting control, and the other reoriented models without daylighting control, and with daylighting control	200
Figure 6-37	Existing Building **(NE-SE-SW Zone** 0-4)	202
Figure 6-38	Reoriented Building 20°(**NE-SE-SW Zone** 0-4)	202
Figure 6-39	Reoriented Building 10°(**NE-SE-SW Zone** 0-4)	202
Figure 6-40	Reoriented Building (**E-S Zone** 0-4)	202
Figure 6-41	Existing Building **(NE-SE Zone** 0-5)	203

Figure 6-42	Reoriented Building 20˚(**NE-SE Zone** 0-5)	203
Figure 6-43	Reoriented Building10˚ (**NE-SE Zone** 0-5)	203
Figure 6-44	Reoriented Building (**North Zone** 0-5)	203
Figure 6-45	Monthly cooling energy consumption For zone (0-4) in the four investigated orientations	206
Figure 6-46	A comparison between lighting loads for zone 0-4 through the base case without daylighting control and the other reoriented models with daylighting controls	207
Figure 6-47	A comparison between cooling loads for zone 0-4 through the base case without daylighting control, and the other reoriented models are without daylighting control, and with daylighting control	207
Figure 6-48	Monthly cooling energy consumption For zone (0-5) through the four investigated orientations	208
Figure 6-49	A comparison between lighting loads for zone 0-5 through the base case without daylighting control and the other reoriented models with daylighting controls	210
Figure 6-50	A comparison between cooling loads for zone 0-5 through the base case without daylighting control, and the other reoriented models are without daylighting control, and with daylighting control	210
Figure 6-51	Existing Building **(NE-NW-SW Zone** 1-2)	211
Figure 6-52	Reoriented Building 20˚ (**NE-NW-SW Zone** 1-2)	211
Figure 6-53	Reoriented Building10˚ (**NE-NW-SW Zone** 1-2)	211
Figure 6-54	Reoriented Building (**N-W-S Zone** 1-2)	211
Figure 6-55	Existing Building **(NE-SE-SW Zone** 1-3)	212
Figure 6-56	Reoriented Building 20˚(**NE-SE-SW Zone** 1-3)	212
Figure 6-57	Reoriented Building10˚ (**NE-SE-SW Zone** 1-3)	212
Figure 6-58	Reoriented Building (**N-E-S Zone** 1-3)	212
Figure 6-59	Monthly cooling energy consumption For zone (1-2) through the four investigated orientations	215
Figure 6-60	A comparison between lighting loads for zone 1-2 through the base case without daylighting control and the other reoriented models with daylighting controls	216
Figure 6-61	A comparison between cooling loads for zone 1-2 through the base case without daylighting control, and the other reoriented models without daylighting control, and with daylighting control	216
Figure 6-62	Monthly cooling energy consumption For zone (1-3) in the four investigated orientations	217
Figure 6-63	A comparison between lighting loads for zone 1-3 through the base case without daylighting control and the other reoriented models with daylighting controls	219

Figure 6-64	A comparison between cooling loads for zone 1-3 through the base case without daylighting control, and the other reoriented models without daylighting control, and with daylighting control	219
Figure 6-65	Existing Building **(NE-NW-SW Zone** 2-2)	220
Figure 6-66	Reoriented Building 20˚ (**NE-NW-SW Zone** 2-2)	220
Figure 6-67	Reoriented Building10˚ (**NE-NW-SW Zone** 2-2)	220
Figure 6-68	Reoriented Building (**N-W-S Zone** 2-2)	220
Figure 6-69	Existing Building **(NE-SE-SW Zone** 2-3)	221
Figure 6-70	Reoriented Building 20˚ (**NE-SE-SW Zone** 2-3)	221
Figure 6-71	Reoriented Building10˚ (**NE-SE-SW Zone** 2-3)	221
Figure 6-72	Reoriented Building (**N-E-S Zone** 2-3)	221
Figure 6-73	Monthly cooling energy consumption For zone (2-2) in the four investigated orientations	224
Figure 6-74	A comparison between lighting loads for zone 2-2 through the base case without daylighting control and the other reoriented models with daylighting controls	225
Figure 6-75	A comparison between cooling loads for zone 2-2 through the base case without daylighting control, and the other reoriented models without daylighting control, and with daylighting control	225
Figure 6-76	Monthly cooling energy consumption For zone (2-3) in the four investigated orientations	227
Figure 6-77	A comparison between lighting loads for zone 2-3 through the base case without daylighting control and the other reoriented models with daylighting controls	228
Figure 6-78	A comparison between cooling loads for zone 2-3 through the base case without daylighting control, and the other reoriented models are without daylighting control, and with daylighting control	228
Figure 6-79	A comparison between cooling loads for each zone through the modified model with 0.0˚ N, without daylighting control	230
Figure 6-80	A comparison between cooling loads for each zone through the modified model with 0.0˚ N, with daylighting control	230
Figure 6-81	Alaraby Bank First floor	241
Figure 6-82	WWR on south west facade	241
Figure 6-83	Existing building (Base Case) With WWR	243
Figure 6-84	Modified building with WWR 40%	243
Figure 6-85	Modified building with WWR 30%	243
Figure 6-86	Modified building with WWR 20%	243
Figure 6-87	Monthly cooling energy consumption though the four investigated WWRs	245
Figure 6-88	Base Case (NW-SE- SW Zone 0-2 with WWR	246
Figure 6-89	First Case (NW-SE- SW Zone 0-2 with WWR 40%)	246

Figure 6-90	Second Case (NW-SE- SW Zone 0-2 with WWR 30%)	246
Figure 6-91	Third Case (NW-SE- SW Zone 0-2 with WWR 20%)	246
Figure 6-92	Base Case (South West Zone 0-3) with WWR 78%)	248
Figure 6-93	First Case (South West Zone 0-3 with WWR 40%)	247
Figure 6-94	Second Case (South West Zone 0-3 with WWR 30%)	247
Figure 6-95	Third Case (South West Zone 0-3 with WWR 20%)	247
Figure 6-96	Monthly cooling energy consumption For zone (0-2) with the four investigated WWR	250
Figure 6-97	A comparison between lighting loads for zone 0-2 through the base case without daylighting control and the other simulated models with different WWRs and with daylighting controls	251
Figure 6-98	A Comparison between monthly cooling loads for Zone 0-2 through the base case with WWR 43% and the other simulated models with and without daylighting control	251
Figure 6-99	Monthly cooling energy consumption For zone (0-3) with the four investigated WWR	253
Figure 6-100	A comparison between lighting loads for zone 0-3 through the base case without daylighting control and the other simulated models with different WWRs and with daylighting controls	254
Figure 6-101	A Comparison between monthly cooling loads for Zone 0-3 through the base case with WWR 62% and the other simulated models with and without daylighting control	254
Figure 6-102	Base Case (NE-SE-SW Zone 0-4) with WWR 78%)	256
Figure 6-103	First Case (NE-SE-SW Zone 0-4) with WWR 40%)	256
Figure 6-104	Second Case (NE-SE-SW Zone 0-4) with WWR 30%)	256
Figure 6-105	Third Case (NE-SE-SW Zone 0-4) with WWR 20%)	256
Figure 6-106	Base Case (NE-SE Zone 0-5) with WWR 78%)	257
Figure 6-107	First Case (NE-SE Zone 0-5 with WWR 40%)	257
Figure 6-108	Second Case (NE-SE Zone 0-5 with WWR 30%)	257
Figure 6-109	Third Case (NE-SE Zone 0-5 with WWR 20%)	257
Figure 6-110	Monthly cooling energy consumption For zone (0-4) with the four investigated WWR	260
Figure 6-111	A comparison between lighting loads for zone 0-4 through the base case without daylighting control and the other simulated models with different WWRs and with daylighting controls	261
Figure 6-112	A Comparison between monthly cooling loads for Zone 0-4 through the base case with WWR 48.8% and the other simulated models with and without daylighting control	261
Figure 6-113	Monthly cooling energy consumption For zone (0-5) with the four investigated WWR	263

Figure 6-114	A comparison between lighting loads for zone 0-5 through the base case without daylighting control and the other simulated models with different WWRs and with daylighting controls	264
Figure 6-115	A Comparison between monthly cooling loads for Zone 0-5 through the base case with WWR 47.8% and the other simulated models with and without daylighting control	264
Figure 6-116	Base Case (NE-SW-NW Zone 1-2) with WWR 48.1%)	266
Figure 6-117	First Case (NE-SW-NW Zone 1-2) with WWR 40%)	266
Figure 6-118	Second Case (NE-SW-NW Zone 1-2) with WWR 30%)	266
Figure 6-119	Third Case (NE-SW-NW Zone 1-2) with WWR 20%)	266
Figure 6-120	Base Case (NE-SW-SE Zone 1-3) with WWR 48.1%)	267
Figure 6-121	First Case (NE-SW- SE Zone 1-3) with WWR 40%)	267
Figure 6-122	Second Case (NE-SW- SE Zone 1-3) with WWR 30%)	267
Figure 6-123	Third Case (NE-SW- SE Zone 1-3) with WWR 20%)	267
Figure 6-124	Monthly cooling energy consumption For zone (1-2) with the four investigated WWR	270
Figure 6-125	A comparison between lighting loads for zone 1-2 through the base case without daylighting control and the other simulated models with different WWRs and with daylighting controls	271
Figure 6-126	A Comparison between monthly cooling loads for Zone 1-2 through the base case with WWR 48.06% and the other simulated models with and without daylighting control	271
Figure 6-127	Monthly cooling energy consumption For zone (1-3) with the four investigated WWR	273
Figure 6-128	comparison between lighting loads for zone 1-3 through the base case without daylighting control and the other simulated models with different WWRs and with daylighting controls	274
Figure 6-129	A Comparison between monthly cooling loads for Zone 1-3 through the base case with WWR 46.00% and the other simulated models with and without daylighting control	274
Figure 6-130	Base Case (NE-SW-NW Zone 2-2) with WWR 48.1%)	276
Figure 6-131	First Case (NE-SW- NW Zone 2-2) with WWR 40%)	276
Figure 6-132	Second Case (NE-SW- NW Zone 2-2) with WWR 30%)	276
Figure 6-133	Third Case (NE-SW- NW Zone 2-2) with WWR 20%)	276
Figure 6-134	Base Case (NE-SW-SE Zone 2-3) with WWR 46%)	277
Figure 6-135	First Case (NE-SW- SE Zone 2-3) with WWR 40%)	277
Figure 6-136	Second Case (NE-SW- SE Zone 2-3) with WWR 30%)	277
Figure 6-137	Third Case (NE-SW- SE Zone 2-3) with WWR 20%)	277
Figure 6-138	Monthly cooling energy consumption For zone (2-2) with the four investigated WWR	280